

Estimated Proposal Price for solar watt power 8.8kWp 8kW On/Off Hybrid inverter(single phase), Battery Capacity 20.48kWh (Classic Version) Solar System Installation for South Dagon Branch.

No.	Item	Qty	Unit	Price	Amount
1	Pipe and Trunking	1	set	200,000	200000
2	Earthing	1	set	200,000	200000
3	63A VA protector	2	pcs	48,000	96000
4	63A Change Breaker	1	pcs	60,000	60000
5	63A AC Breaker (Chint)	2	pcs	17,500	35000
6	6mmsq AC Cable	50	m	7,000	350000
7	6mmsq Earth Cable	50	m	6,800	340000
8	No.00 Panel	1	pcs	50,000	50000
9	35-8 Cable Lug	4	pc	3,900	15600
10	50-8 cable lug	8	pc	4,800	38400
11	Stopper	12	pc	500	6000
12	Buabar 40*5	16	In	7,000	112000
13	4/9 Join Box	2	pcs	4,900	9800
14	25mm Adaptor	15	pcs	1,000	15000
15	M 7 Wallplug	2	dz	1,000	2000
16	1 1/2 black screw	2	dz	1,000	2000
17	12 နက်တိုင် 1 1/2	8	set	600	4800
18	12 နက်တိုင် 1/2	8	pcs	300	2400
19	SM-51	4	pcs	3,500	14000
20	25mm flexible pipe	20	Ft	500	10000
Total					1563000



Ref No: QUO/RET/2024/11/039
Date: 19 - Nov - 2024

Com : SDG Branch
To : Ko Min Thura
Ph : 09-770933263
Tsp : Southdagon Township
Sub : Estimated Proposal Price for Solar watt power 8.8kWp, Inverter Capacity 8kW, Battery Capacity 20.48kWh On,Off Grid Hybrid (Single Phase) Solar Energy Storage System

Dear Sir,
We would like to offer you our quality product which is suitable to use for your business with the best price as follows.

NO.	ITEM	DESCRIPTION	Size	Qty	Unit	Price	Amount (MMK)
						MMK/UNIT	
1	Solar, Mounting Structure and Accessories	Number of PV module (Matador Lectro)	550W	16	pcs	475,000	7,600,000
		Mounting structure and Accessories for Rooftop		1	lot	1,751,040	1,751,040
2	Inverter	Deye 8kW On,Off grid Hybrid Inverter (Single Phase)(SG05L1P New Model)	8kW	1	pc	6,150,000	6,150,000
3	Battery	Matador Lectro LifePO4 Battery (51.2V 200Ah) (Classic Version)	10.24kWh	2	pc	6,650,000	13,300,000
4	Solar Cable ,AC Cable and Earth Cable	Solar Cable (Estimated Length)	4mm ²	200	M	3,500	700,000
		AC Cable (Estimated Length)	6mm ²	50	M	7,000	350,000
		Earth Cable (Estimated Length)	6mm ²	50	M	3,500	175,000
5	Combiner Boxes, PVC Trunking, Pipe and Accessories (AC & DC)	Combiner Box For AC, DC Termination & Battery MC & Connector		1	lot	4,966,400	4,966,400
		PVC Trunking					
		Conduit Pipe, Saddle and Clips					
		Cu Busbar for Battery Termination					
		Battery Breaker (DC)					
		DC Solar Breaker					
		DC Fuse & Holder					
		DC Surge Protector (SPD)					
		AC Breaker (MCB), for grid input					
		AC Breaker (MCB), for load output					
		VA Protector					
Accessories for Termination (DC & AC)							
6	Earthing System	Earthing System Installation and Materials		1	lot	350,000	350,000
7	Installation, Testing & Commissioning	Installation, Testing & Commissioning		1	lot	1,600,000	1,600,000
		Transportation Charges for Materials		1	lot	200,000	200,000
Net Total							37,317,440

Quotation items may be changed depend on the site condition and additional cost must be pay by customer.

Price Validity : 1 Day from the date of this quotation.
 Delivery : Ex-Stock (Subject to prior sales)
 Payment Terms : 70% Downpayment and 30% after installation/testing.
 Warranty : Solar Panel 12 Years
 : On,Off Grid Hybrid Inverter (2 years Product Warranty + 1 Year Service Warranty)
 : Lithium Battery (3 years Product Warranty + 2 Years Service Warranty)
 : System Warranty 1 Year (Customer have to pay travelling cost within system warranty 1 Year)

Thank & Best Regards,

Name : Win Yan Paing
 Position : Sale Man
 Contact No : 09448094199
 Branch : RE BUJ

