

**Estimated Proposal Price for Solar System with Solar Watt Power 8.8kWp, Inverter Capacity 8kW,
Battery 14.336kWh (With Display) for Ko Bo Bo Min Thu.**

No.	Item	Qty	Unit	Price	Amount
1	Pipe and Trunking	1	set	200,000	200000
2	Earthing System	1	set	150,000	150000
3	16mmsq AC Cable	20	m	25,000	500000
4	SM-S1	4	pcs	3,300	13200
5	Buabar 40*5	16	ln	7,000	112000
6	4/9 Join Box	2	pcs	15,500	31000
7	12 x 1" Net set	6	set	600	3600
8	12 x1/2 Net set	8	pcs	350	2800
9	25mm Adaptor	15	pcs	900	13500
10	Stopper	10	pcs	600	6000
11	No. 3 panel	2	pcs	145,000	290000
12	No. 00 penel	2	pcs	51,000	102000
13	UK Terminal Block	4	pcs	22,000	88000
14	100A 4Poles MCCB (Hyundai)or Equivalent	2	pcs	220,000	440000
15	40kA AC SPD 4poles (Himel)	2	pcs	150,000	300000
16	100A or 63A Change over	1	pcs	430,000	430000
17	63A 2Poles AC Breaker	2	pcs	25,000	50000
18	50-8 Cable Lug	16	pc	4,800	76800
19	35-8 Cable Lug	6	pc	3,850	23100
Total					2,832,000
	Installation and labour charges -	50,000			

To : Ko Bo Bo Min Thu
 Ph : 09254006118
 Tsp : No.23 PPYIHTAUNG SU STREET(NGA/KHA)QUARTER,THINGANGYUN TOWNSHIP,YANGON
 Site : No.23 PPYIHTAUNG SU STREET(NGA/KHA)QUARTER,THINGANGYUN TOWNSHIP,YANGON

Dear Sir,
 We would like to offer you our quality product which is suitable to use for your business with the best price as follows;

NO.	ITEM	DESCRIPTION	Size	Qty	Unit
1	Solar, Mounting Structure and Accessories	Number of PV module (Matador Lectro)	550W	16	pcs
		Mounting structure and Accessories for Rooftop		1	Lot
2	Inverter	Matador Lectro/Deye 8kW On/Off grid hybrid inverter (Single Phase)(SG04LP1 New Model)	8kW	1	pc
3	Battery	Matador Lectro LiFePO4 Battery (51.2V 280Ah) (Without Display)	14.34kWh	1	pc
4	Solar Cable ,AC Cable and Earth Cable	Solar Cable (Estimated Length)	6mm ²	200	M
		Earth Cable (Estimated Length)	4mm ²	20	M
		AC Cable (Estimated Length)	10mm ²	20	
		AC Cable (Estimated Length)	16mm ²	20	M
5	Combiner Boxes, PVC Trunking, Pipe and Accessories (AC & DC)	Combiner Box For AC, DC Termination & Battery		1	Lot
		MC 4 Connector			
		PVC Trunking			
		Conduit Pipe, Saddle and Clips			
		Cu Busbar for Battery Termination			
		Battery Breaker (DC)			
		DC Solar Breaker			
		DC Fuse&Holder			
		DC Surge Protector (SPD)			
		AC Breaker (MCB), for grid input			
AC Breaker (MCB), for load output					
VA Protector					
Accessories for Termination (DC & AC)					
6	Earthing System	Earthing System Installation and Materials		1	lot
7	Installation, Testing & Commissioning	Installation, Testing & Commissioning		1	lot
8	Transportation Charges	Transportation Charges			