

Estimate Material list 200 KW On-Grid Solar System (555 Plastic)

| Sr | Description | Size | Qty | Unit | Rate (MMK) | Rate (MMK) | Remark | |
|--------------------------------|---|--------------------|------|--------|------------|-------------------|--|--|
| Cable & Accessories | | | | | | | | |
| 1 | CU/XLPE/PVC Cable (AC) | 70 mm ² | 120 | meter | 56,400 | 6,768,000 | Get (2) Quotation Base On Exchange Rate | |
| 2 | Metal Truncking (1.0mm thickness) | 100*75mm | 110 | pcs | 109,000 | 11,990,000 | Get (2) Quotation Base On Exchange Rate | |
| 3 | L Feet | - | 902 | pcs | 5,800 | 5,231,600 | Get (1) Quotation | |
| 4 | Earthing Clip | - | 991 | pcs | 400 | 396,400 | | |
| 5 | Walk Way | (425x30x1975)m | 99 | pcs | 181,700 | 17,988,300 | Get (1) Quotation | |
| 6 | C clamp (for walk way) | (M8*35)mm | 1089 | pcs | 2,000 | 2,178,000 | | |
| 7 | M clamp (for walk way) | (M8*35)mm | 218 | pcs | 3,300 | 718,740 | | |
| 8 | C purlin | (800)mm | 400 | pcs | 11,150 | 4,460,000 | <p>ကုန်မာဆိုင်များနှင့် ဆောက်လုပ်ရေးပစ္စည်းဆိုင်မှ ပြား၊ ဗူး ဝယ်ရမည့်ပစ္စည်းများဖြစ်ပါသည်။</p> <p>၎င်းဆိုင်လိပ်စာများမှာ စော်ဘွားကြီးကုန်း၊ တောင်ဘုံ၊ လှိုင်သာယာ၊ ဘုရင့်နောင် နှင့် မန္တလေး။ (1.03.2025 မှ 11.03.2025)</p> <p>ရက်အထိခံစမ်းထားသော ဈေးနှုန်းများဖြစ်ပါသည်။ ဈေးနှုန်းအပြောင်းအလဲ ရှိနိုင်ပါသည်။</p> | |
| 9 | Earth Cable | 6mm | 3 | coil | 419,102 | 1,257,306 | | |
| 10 | Cable Lug | 70 mm ² | 25 | pcs | 8,000 | 200,000 | | |
| 11 | Cable Lug | 35mm ² | 20 | pcs | 2,000 | 40,000 | | |
| 12 | Cable Endcup (R,Y,B,N) | 70 mm ² | 10 | pcs | 470 | 4,700 | | |
| 13 | Compound Tape | - | 2 | pcs | 32,000 | 64,000 | | |
| 14 | Cable Ties (Black) | - | 30 | bag | 17,500 | 525,000 | | |
| 15 | Angle iron | 1 1/2 | 30 | pcs | 56,500 | 1,695,000 | | |
| 16 | Red Oxide | - | 2 | gallon | 54,000 | 108,000 | | |
| 17 | Cable Gland | No.19 | 16 | pcs | 1,600 | 25,600 | | |
| 18 | Pipe accessories (El bow, Socker, etc...) | - | 1 | lot | 300,000 | 300,000 | | |
| 19 | Silicon | - | 20 | pcs | 15,000 | 300,000 | | |
| 20 | Copper Earth rod | - | 20 | pcs | 38,000 | 760,000 | | |
| 21 | Test Link Box | - | 2 | pcs | 22,000 | 44,000 | | |
| 22 | Earth powder | 25kg | 3 | bag | 180,000 | 540,000 | | |
| 23 | Conduct pipe | 25 | 3 | pcs | 4,900 | 14,700 | | |
| 24 | Wire Tape(R,Y,B,N) | - | 8 | coil | 2,800 | 22,400 | | |
| 25 | General Accessories | | | | | 500,000 | | |
| Total | | | | | | 56,131,746 | | |

No (519 521), Myanmar Padauk Business Centre, Lower Pazundaung Road, Pazundaung Township, Yangon, Myanmar-11171

Quotation

Customer's Name : U Kaung Myat Kyaw (U MKG)
Phone : +9592021850
Address : YGN

Quotation No : 001-03 YGN
Salesman's Name : Mya Yee Win
Phone : 09454205881
Date : 5.3.2025

| Sr.No | DESCRIPTION | UNIT | QTY | UNIT PRICE | Discount | Net Amount | Remark |
|--------------|--|-------|-----|------------|----------|------------------|---------|
| 1 | 0.6 1kV Cu XLPE PVC 1Cx70mm ² (Koryo-Korea) | Meter | 120 | 56,400 | 15% | 5,752,800 | instock |
| Total | | | | | | 5,752,800 | |

Terms & Condition

- After order confirm, not returnable, refundable or exchangeable.
- No claim will be considered after order confirmed.
- Deposit payment process after order confirmed and final payment process after products delivery.
- Price validity will change by daily exchange rate.
- Delivery time will depend on order confirmed.

Yangon : +959 8000 177 51 , +959 40 8088 018, Davao : +959 457 3668 63, +959 8000 144 06, Taunggyi : +959 445 576 001, +959 8000 177 51, +959 8000 144 03
Mawmyath : +959 400 606 042, +959 8000 177 51, +959 8000 144 07, Patheingyi : +959 8000 144 06, +959 8000 177 56

For Enquiry, Please contact +959 8000 177 51, Mail : md@mppower.com.mm

Thank You For Your Business!



CLASSIC

Electrical & Engineering Co Ltd

Amendment :

Sales Quotation

Region Name :

Buyer,
Winning Way Co.,Ltd

Branch Name No.134, Road-2, Zaygabar Garden City, Mingalardon Industrial Zone, Mingalardon Township, Yangon, Myanmar.

Division Name : Industrial Zone, Mingalardon Township, Yangon, Myanmar.

Category Name :

Sales person : Aung Thiha

Phone No : 09977756257

Quotation No :

Date : 5.03.2025

Validity :

Exp Date :

Kind Attention ,
Ko Kaung Myat Kyaw

| Sr. No. | Description | Quantity | Unit | Rate/ Unit (MMK) | Disc (%) | Total Amount (MMK) | Remark |
|------------------|-----------------------|----------|------|------------------|----------|--------------------|--------|
| 1 | 1CxCu/XLPE/PVC 70mmsq | 120 | Mtr | 78300 | 0 | 9,396,000 | |
| Gross Amount | | | | | | 9,396,000 | |
| Net Amount (MMK) | | | | | | 9,396,000 | |

Payment Term :

Payment Against Invoice

Terms and Condition :

Not Authorised

For, CLASSIC ELECTRICAL & ENGINEERING CO., LTD.

On Behalf of,

Aung Thiha

(Authorised Signatory)

Prepared by

(Name, Sign & Company Seal)

To : Daw Swe Swe Myint
Ph : 09-2004602
Com : 555 Plastic
Add : Mandalay
Sub : Estimated Proposal Price for 200kW On Grid Solar System with Solar Watt Power 211.2kWp and Inverter Capacity 200kW.

Dear Sir,

We would like to offer you our quality product which is suitable to use for your business with the best price as follows;

| NO. | ITEM | DESCRIPTION | Size | Qty | Unit | Price | Amount (MMK) |
|------------------|---|--|--------------------|------|------|------------|--------------------|
| | | | | | | MMK/UNIT | |
| 1 | Solar, Mounting Structure and Accessories | Number of PV module (Matador Lectro) | 550W | 384 | pcs | 452,000 | 173,568,000 |
| | | Roof Top Aluminium Structure and accessories | | 1 | lot | 39,578,720 | 39,578,720 |
| 2 | InverterSolar Cable, AC Cable and Earth Cable | 100 kW Ongrid inverter (Matador Lectro) | 100 kW | 2 | pc | 14,464,000 | 28,928,000 |
| | | Solar DC Cable (Red & Black)(Estimated) | 4 mm ² | 3400 | M | 3,616 | 12,294,400 |
| | | Cu/XLPE/PVC (Estimated) | 70mm ² | 60 | M | 90,400 | 5,424,000 |
| | | Cu/XLPE/PVC (Estimated) | 185mm ² | 60 | M | 226,000 | 13,560,000 |
| | | Earth Cable (Estimated) | 35mm ² | 100 | M | 58,760 | 5,876,000 |
| 3 | Power Distribution Panel & Accessories | Solar Power Distribution Panel (DC & AC) | | 1 | lot | 31,640,000 | 31,640,000 |
| | | Accessories for Termination (DC & AC) | | | | | |
| 4 | Maintenance Walk Way | Maintenance Walk Way | | 1 | lot | 31,640,000 | 31,640,000 |
| 5 | Pipe, Ladder,Trunking and Accessories | Pipe, Ladder,Trunking and Accessories | | 1 | lot | 15,820,000 | 15,820,000 |
| 6 | Earthing for Solar System | Earthing for Solar System | | 1 | lot | 12,656,000 | 12,656,000 |
| 7 | Installation, Testing and Commissioning charges | Solar installation Charges | | 1 | lot | 42,958,080 | 42,958,080 |
| | | DC Cable Installation Charges | | | | | |
| | | AC Cable Installation Charges | | | | | |
| | | Testing and Commissioning Charges | | | | | |
| 8 | Transportation Charges | Transportation Charges | | 1 | lot | 6,056,800 | 6,056,800 |
| Net Total | | | | | | | 420,000,000 |

Quotation items may be changed depend on the site condition and additional cost must be pay by customer.

Price Validity : 7 Days from the date of this quotation.
 Delivery : Negotiable
 Payment Terms : 70% down payment, 30% payment after testing within 7days.
 Warranty : System Warranty 1 Year.
 : On Grid Inverter 3 Years
 : Solar Panel 12 Years

Thank & Best Regards,

Name : Kyaw Lin Thu
 Position : Sales Man
 Contact No : 09450258982
 Branch : Mandalay Branch



Sayar Aye Min Htoon
online



UMG

ADVANCE REQUEST FORM

| | | | |
|-----------------|-----------------------|--------------------|-------------------------|
| Requester Name | Naun Oo ✓ | Budget Type | Include Budget ✓ |
| Department Name | | Request Type | Advance Payment ✓ |
| Request Date | | Advance Date | 2023/02/01 ✓ |
| Payment Number | RDV-UMG-0001-00-00009 | Prepared By | SSA Budget Allocation ✓ |
| Payment Method | Cash Bank | Issuance Statement | 48 Working Hour ✓ |
| Payment Account | SA 5517460 | By | |
| Currency | MMK | Last Approval By | SSA Budget Allocation ✓ |
| Exchange Rate | 4.400 | | |

| No. | Description | Department | Budget Amount | Balance |
|-----|---|---|-----------------|-----------------|
| 1 | Advance request for Materials Charge of 200KW On Grid Solar System Installation (Cash Bank Working Hour 48hr) Myanmar General Allocation 1.00hr. (See also due 19/01/23) (Budget Allocation) Total 41W 56,131,746 MMK | Project Infrastructure Infrastructure | 56,131,746.00 ✓ | Advance Request |

Expense Total 56,131,746.00 ✓
Amount Request 26,131,746.00 ✓

Note:

| | | |
|---------------|------------------|------------------|
| Approved By | SSA | CM/AGP |
| Name: Naun Oo | Name: U Tun Aung | Name: U Tun Aung |
| NRC No: | NRC No: | NRC No: |
| Date: | Date: | Date: |
| Remark: | Remark: | Remark: |

Dear Sayar..
555 Plastic 200KW On Grid Solar System Installation အတွက် Materials Charges Advance - 56,131,764 MMK တင်ရာတွင် အပြည့်မထုတ်ပဲ ပထမတစ်ခါအတွက် Advance - 26,131,746 MMK ပဲ ထုတ်ယူကြောင်းကို သိရှိခြင်း Approve တောင်းခံပါတယ် ဆရာ.. 🙏

2:37 PM ✓



Nann Oo
Dear Sayar.. 555 Plastic 200KW On Grid...

Noted.
Please continue the process.

10:54 PM

ဟုတ်ကဲ့ပါ ဆရာ. 10:55 PM ✓

Message

