


Estimate Material list 50 KW Hybrid Solar System (Chan Myae Hospital)

Sr	Description	Size	Qty	Unit	Rate (MMK)	Rate (MMK)	Remark	
Cable & Accessories								
1	CU/XLPE/PVC Cable (AC)	35 mm2	160	meter	25,542	4,086,720	Get (2) Quotation Base On Exchange Rate	
2	CU/PVC Earth Cable (G/Y)	16 mm2	50	meter	13,160	658,000		
3	CU/PVC Earth Cable (G/Y)	6 mm2	100	meter	5,922	592,200		
4	Single Core flexiable cable(DC)	2.5 mm2	1	Coil	203,900	203,900	<p>ကုန်မှာဆိုင်များနှင့် ဆောက်လုပ်ရေးပစ္စည်းဆိုင်များမှ ဝယ်ရမည့်ပစ္စည်းများဖြစ်ပါသည်။ ၎င်းဆိုင်လုပ်စာများမှာ စော်ဘွားကြီးကုန်း၊ တောင်ဒဂုံ၊ ညောင်ဦး၊ ပခုက္ကူ။ (21.07.2025 မှ 25.07.2025) ရက်အထိစုံစမ်းထားသော ဈေးနှုန်းများဖြစ်ပါသည်။ ၎င်းဈေးနှုန်းအပြောင်းအလဲ ရှိနိုင်ပါသည်။</p>	
5	Change Over Switch	200A	1	pcs	760,000	760,000		
6	Cable Lug	35 mm2	20	pcs	3,800	76,000		
7	Cable Lug	16 mm2	12	pcs	1,700	20,400		
8	Cable Lug	6 mm2	10	pcs	900	9,000		
9	L Feet	-	169	pcs	6,500	1,098,500		
10	Earthing Clip	-	212	pcs	500	106,000		
11	Cable Endcup (R,Y,B,N)	35 mm2	10	pcs	1,560	15,600		
12	Compound Tape	-	2	pcs	32,000	64,000		
13	Cable Ties (Black)	-	10	bag	17,500	175,000		
14	Angle iron	1 1/2	20	pcs	28,900	578,000		
15	Grey Oxide	-	1	gallon	55,000	55,000		
16	Cable Gland	No.36	10	pcs	1,600	16,000		
17	Pipe accessories (El bow, Socker, etc...)	-	1	lot	300,000	300,000		
18	PVC pipe	4"	15	pcs	52,700	790,500		
19	Copper Earth rod	-	20	pcs	38,000	760,000		
20	Test Link Box	-	2	pcs	22,000	44,000		
21	Earth powder	25kg	2	bag	180,000	360,000		
22	Conduct pipe	25	10	pcs	6,300	63,000		
23	Wire Tape(R,Y,B,N)	-	8	coil	2,800	22,400		
24	General Accessories	-	-	-	500,000	500,000		
Labours and Installation Charges								
25	Labours and installation Charges	-	-	-	1,000,000	1,000,000		
Total						12,354,220		

Request By



Name: Nann Oo
Position: Sr.Staff
Department: Project Implimentation

Acknowledged By (DH)



Name: Kaung Myat Kyaw
Position: DH
Department: Project Implementation

Approved By



Name: Phyo Thu
Position: GM
Department: Management

To : Dr. Mg Mg Swe
Com : Chan Myae Hospital
Ph : 09-777159159
Add : Pakokku Tsp
Sub : Estimated proposal price for 50kW Hybrid Solar System (50kW, 50kWp)
Dear Sir,

Ref No: QUO/REN/PRS/2024/07/009 (Rev-4)
Date: 7 - Jul - 2025

We would like to offer you our quality product which is suitable to use for your business with the best price as follows;

Description	Size	Qty	Unit	Price	Amount (MMK)
				MMK/UNIT	
No.1 Solar Panel					
Matador Lectro - Bifacial Solar Panel (MLPV-625-33V-MHDRz)	625W	80	pcs	395,000	31,600,000
No.2 Solar Mounting Structure					
Aluminium Mounting Structure and Accessories		1	Lot	11,300,000	11,300,000
No.3 Inverter					
DEYE-HV On/Off Grid Hybrid inverter (SUN-50K-SG01HP3-EU-BM4) (Three Phase)	50kW	1	pc	22,000,000	22,000,000
No.4 Battery					
DEYE-HV LiFePO4 Battery (BOS-GM5.1)	5.12kWh	-	pcs	Optional	
Battery Rack (3U-HRACK)		-	pc		
Control Box (HVB 750V/100A-EU)		-	pc		
No.5 Cables (AC, DC, Ground)					
DC Cables (CU, XLPO/XLPO, TUV rated 1.5kV) (PN Tech) <i>(Estimated Length)</i>	1C x 4mm ²	600	M	3,400	2,040,000
AC Cable (CU, XLPE/PVC, 0.6/1.1kV) (Kyoro or Equivalent) <i>(Estimated Length)</i>	1C x 35mm ²	60	M	36,000	2,160,000
AC Cable (CU, XLPE/PVC, 0.6/1.1kV) (Kyoro or Equivalent) <i>(Estimated Length)</i>	1C x 50mm ²		M	Optional	
Ground Cable (Cu/PVC, 750V) (Kyoro or Equivalent) <i>(Estimated Length)</i>	1C x 6mm ²	100	M	9,000	900,000
Ground Cable (Cu/PVC, 750V) (Kyoro or Equivalent) <i>(Estimated Length)</i>	1C x 16mm ²	50	M	17,000	850,000
No.6 Cable Trunking and Accessories					
Epoxy Paint Coated Metal Trunking, Pipe, Ladder and Accessories		1	lot	2,500,000	2,500,000
No.7 Electrical Panel and Protection System					
Power Distribution Panel (AC & DC) 200A Change Over (Havells or Equivalent) Cable lugs & Cable gland MC 4 Connector AC MCCB 200 (for Grid Input) AC MCCB 125(for Load Output) 25A DC MCB DC SPD AC SPD Current Transformer Over Current Protector Accessories for Termination (DC & AC)		1	Lot	15,750,000	15,750,000


No.8 Earthing System					
Earth Rod					
Earth Pit					
Earth Cable (35mm ²)		1	Lot	3,000,000	3,000,000
Earthing Accessories					
Earthing System Installation					
No.9 Design, Installation, Testing and Commissioning					
Site Survey					
Drawing (Electrical & Mechanical)					
Safety, PPE					
Project Management					
Mounting Structure and Panel Installation		1	Lot	10,000,000	10,000,000
Inverter Installation					
Electrical Wiring System Installation					
System Testing and Commissioning					
Operation Training					
Project & Documents Handover					
No.10 Transportation					
Material Transportation		1	Lot	2,000,000	2,000,000
Travelling, Accommodation and Meals for Service Team		1	Lot	2,700,000	2,700,000
				Net Total (MMK)	106,800,000

Quotation items may be changed depend on the site condition and additional cost must be pay by customer.

Price Validity : 3 Days from the date of this quotation.
 Delivery : Negotiable
 Payment Terms : 70% down payment, 30% payment after testing within 7days.
 : System Warranty 1 Year
 Warranty : Solar Panel 12Years
 : Hybrid Inverter 5Years (3Years Parts and Service + 2Years Service)

Name : Hay Mar Soe
 Position : Project Sales Engineer
 Contact No : 09254074920
 Branch : Head Office





CUSTOMER CONFIRMATION ORDER FORM

CCU Date : 14.7.2025
 CCU No : UCCO1NYU1RE1202510710011
 Company Name : Chanmyae Hospital
 Contact Person Name : Dr Maung Maung Swe
 Address :
 Phone Number : 09-977159159
 Customer NRC No : 8/Paktha ka (w) 018519.
 Brand Name : matador lectro
 Machine Model : 50 kw
 Machine Price : 975 lakhs.
 Machine Qty : 1
 Import License & Duty Charges :
 Warranty Term : 12 yrs warranty solca, 5yrs hybrid inverter 3yrs parts & service + 2 yrs service
 Estimate Delivery Time : within August '25
 Payment Term : 40% DP, 30% on delivery & 30% after installation.
 FOC : -
 Discount : -
 Business Type : Hospital
 Jobsite Location : Pakkoku
 Lucky Money Amount : -
 Receiver Name (Lucky Money) : -
 Receiver Ph No. (Lucky Money) : -
 Receiver Address (Lucky Money) : -
 Receiver NRC No (Lucky Money) : -
 Sales Person Name : Zaw Htay Aung.
 Branch or BU Name : Nyaung U

Note : I hereby understand that the deposit paid to UMG Co., Ltd. is non-refundable when I fail to proceed the sales process for any reason.

Sold by	Acknowledged by	Approved by
Signature : Name : Zaw Htay Aung	Signature : Name : <i>[Signature]</i> Name : Zaw Htay Aung	Signature : Name : <i>[Signature]</i> NRC No. : 8/Paktha ka (w) 018519
(Sales Person)	(BOH/AGM/GM)	(Customer)

12-NQU-SLS-FRM-001-01

RECEIPT VOUCHER

Customer Name : DR.MAUNG MAUNG SWE Invoice Date :
 Receipt Date : 07/16/2025 Invoice No :
 Receipt Voucher : RV-REN-2025-07-00009 Unit or Part : Unit
 No Last Approval : Posted
 Received Method : Manual Status
 Received Amount : 39,000,000.00 K
 Exchange Rate : 4,480.0
 Currency : MMK

No	Description	Reference	Amount
1	RV-REN-2025-07-00009		39000000.0

Total Amount : 39,000,000.00
K

Note: Unit Income
 Dr. Maung Maung Swe (Chan Myae Hospital)
 UCCO/NYU/RE/2025/07/0011
 50kW/50kWp On and Off Grid Hybrid Solar System -1 Set
 Downpayment 40% MMK =39,000,000/-KBZ call deposit

Sale Dept		Finance & Account Dept		Customer		Received By	
Name	:	Name	:	Name	:	Name	:
NRC No	:	NRC No	:	NRC No	:	NRC No	:
Date	:	Date	:	Date	:	Date	:

(19.521), Myanmar Padauk Business Centre, Lower Pazundaung Road, Pazundaung Township, Yangon, Myanmar-11171

Quotation

Customer's Name : U Kaung Myat Kyaw Winning Way Co.,Ltd
 Phone : +9592021880
 Address : YGN

Quotation No : 020-06 YGN
 Saleman's Name : Mya Yee Win
 Phone : 09454205881
 Date : 25.7.2025

CU
CU
CU

Sr No	DESCRIPTION	UNIT	QTY	DIS PRICE	Discount	Net Amount	Remark
1	0.6 1kV Cu PVC 1Cx16mm ² Earth Cable(Koryo)	Meter	50	14,000	6%	658,000	
2	0.6 1kV Cu PVC 1Cx6mm ² Earth Cable(Koryo)	Meter	100	6,300	6%	592,200	
3	0.6 1kV Cu XLPE PVC 1Cx35mm ² (Koryo)	Meter	160	29,700	14%	4,086,720	
Total						5,336,920	

Terms & Condition

- After order confirm, not returnable, refundable or exchangeable.
- No claim will be considered after order confirmed.
- Deposit payment process after order confirmed and final payment process after products delivery.
- Price validity will change by daily exchange rate.
- Delivery time will depend on order confirmed.

Yangon : +959 8800 177 51 , +959 40 8885 013 , Davao : +959 457 3666 63 , +959 8800 144 05 , Taunggyi : +959 445 378 001 , +959 8800 177 51 , +959 8800 144 03
 Magway : +959 400 686 942 , +959 8800 177 57 , +959 8800 144 07 , Patheingyi : +959 8800 144 06 , +959 8800 177 56

For Enquiry, Please contact : +959 8800 177 51 , Mail : td@mppower.com.mm

Thank You For Your Business

Amendment :

Sales Quotation

Region Name :

Buyer,
Winning Way Co.,Ltd

Branch Name No.134, Road-2, Zaygabar Garden City, Mingalardon Industrial Zone, Mingalardon Township, Yangon, Myanmar.

Division Name : Industrial Zone, Mingalardon Township, Yangon, Myanmar.

Category Name :

Sales person : Aung Thiha

Phone No : 09977756257

Quotation No :

Date : 25.07.2025

Validity :

Exp Date :

Kind Attention ,
Ko Kaung Myat Kyaw

Sr. No.	Description	Quantity	Unit	Rate/ Unit (MMK)	Disc (%)	Total Amount (MMK)	Remark
1	1CxCu/PVC 6mmsq (Y/G)	100	Mtr	6620	36	423,680	
2	1CxCu/PVC 16mmsq (Y/G)	50	Mtr	17320	36	554,240	
3	1CxCu/XLPE/PVC 35mmsq	160	Mtr	39900	36	4,085,760	
Gross Amount						5,063,680	
Net Amount (MMK)						5,063,680	

Payment Term :

Payment Against Invoice

Terms and Condition :

Not Authorised

For, CLASSIC ELECTRICAL & ENGINEERING CO., LTD.

On BeHalf of,

Aung Thiha

(Authorised Signatory)

Prepared by

(Name, Sign & Company Seal)